BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Construction of Building and Development of Govt. School and improvements in school Premises at Jalahalli village in ward no 16.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
112	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintles exceeding 1 m in depth incluidng cost of all materials, labour complete as per specifications.	Sqm	129.16	500.0	Rupees Five Hundred Only
113	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specificaiton. Staircase.	Sqm	26.20	500.0	Rupees Five Hundred Only
114	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	1.38	7500.0	Rupees Seven Thousand Five Hundred Only
115	Providing & removing centering shuttering,strutting, propping etc., and removal of form work for sides & soffits of beams, beam haunchings, cantilever girders, bresumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications.	Sqm	20.76	500.0	Rupees Five Hundred Only
116	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0.345cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms, average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications.	Sqm	8.91	650.0	Rupees Six Hundred Fifty Only
117	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specificaiton.	Sqm	8.91	500.0	Rupees Five Hundred Only
118	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	215.82	1200.0	Rupees One Thousand Two Hundred Only
119	Providing 12mm thick cement plaster in single coat with cement mortar 1:4, to ceiling including rounding off corners wherever required smooth rendering.. Providing and removing scaffolding, including cost of materials, labour, lead, lift, curing complete as per specifications and direction of the Engineer in charge Providing Lime rendering for Plastering to Ceiling including cost of materials, labour, curing complete as per specification.	Sqm	221.19	300.0	Rupees Three Hundred Only
120	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering. : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge for Inside Plastering.	Sqm	371.24	300.0	Rupees Three Hundred Only

For K. DAMODAR & CO.

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK:Construction of Building and Development of Govt. School and improvements in school Premises at Jakkasandra village in ward no 16.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
121	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering. : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering.	Sqm	260.53	300.0	Rupees Three Hundred Only
122	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500.	Tonne	5.65	75000.00	Rupees Seventy Five Thousand Only
123	Providing Sal wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications.	Cum	0.50	110000.0	Rupees One Lakh Ten Thousand Only
124	Providing and fixing factory made splendoor of solid core single leaf rigid composite polymer laminated sal wood, door shutter of required thickness, manufactured out of solid core door conforming to IS 2202 (Part-1) 1991, laminated with 0.8 mm thick polymer, termite, water resistant and fire retardant with superior gluing based on vacuum lamination technology and with various pre moulded design on both faces conforming to IS 6307-1985, using adhesive conforming to IS 4835-1979 and door shuters tested in conformation to IS 4020-1994. The finish of shutters will be TEADK/OAK/CEDAR/ROSE WOOD/ WALNUT, plain colurs WHITE/IVORY/BEIGE/LIGHT GREY. Excluding cost of fixtures and inclusive of supply of shutters to respective work spot. with door shutter 35mm thick.	Sqm	15.36	4000.0	Rupees Four Thousand Only
125	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using threetrack window frame of size 92x31.75mm bottom section 1.3mm thick.weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933kg/m.shutter frame section comprising top and bottom section of size40mmx18mm, wall thickness 1.25mm, weight 0.417 kg./m, shutter sideouter 40mmx18mm, wall thickness 1.25mm, weight 0.417 kg/m, shutterinterlock section 40mmx26.7mm wall thickness 1.1 mm, thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved qualityof fixtures such as aluminium handles tower bolts etc.; providing andfixing 5.5mm, thick plain glass for shutters fitted with rubber beading allaluminium sections including cutting to required length, joints mitredsubdividing the frame tenonned and rivetted, in the assembled frame.stiffened with end clips for corners, angles etc., and fixed to the walls,lintels, floor beams/cills as the case may be, with necessary steelscrews, raul plugs or teak wood gatties including cutting masonry orconcrete and making good the original surface using cement mortar.(using aluminium section powdered coated to a minimum of 60-70 microns with exterior durable pure polyester grade powder o	Sqm	33.75	4000.00	Rupees Four Thousand Only

For K. DAMODAR & CO.

Managing Partner

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Construction of Building and Development of Govt. School and improvements in school Premises at Jalahalli village in ward no 16.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
126	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications.	Kg	708.75	115.0	Rupees One Hundred Fifteen Only
127	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers including cost of all materials cost oif labour and scaffolding etc complete as per the specifications.	Sqm	221.19	70.0	Rupees Seventy Only
128	Providing and applying painting in two coats with plastic Emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge. (with Primer).	Sqm	371.24	100.0	Rupees One Hundred Only
129	Providing and finishing external walls in two coats over one coat of 100% acrylic silicon glazed primer with antifungal paint for top coat of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	260.53	200.0	Rupees Two Hundred Only
130	Applying priming coat over new wood surface and/ or wood based surface after preparing the surface after throughlycleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, completeas per specifications.	Sqm	110.50	70.0	Rupees Seventy Only
131	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood basedsurface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost ofmaterials, labour, complete as per specifications.	Sqm	34.56	100.0	Rupees One Hundred Only
132	Providing and applying enamel metal paint two coats(excluding priming coat) over new steel or other metal surfacebrushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as perspecifications.	Sqm	75.94	100.0	Rupees One Hundred Only
133	Providing and fixing Vitrified glazed tiles, of approved make, quality and colour of size 600x600x10mm thick fixed on bed of 12 thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to match shade of tiles, including providing spacers at required interval and removing stains etc., complete as per specifications.	Sqm	148.39	1000.00	Rupees One Thousand Only
134	Providing and fixing Skirting of 300mm high using prepolished water cut/gang saw of 19mm thick grey granite 0.5mm wide chamfered width and depth and fixing in CM 1:4 of 20mm thick after chipping the walls etc., complete.	Mtr	20.62	900.0	Rupees Nine Hundred Only
135	Flooring with 25mm to 40mm thick polished tandur blue stone slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab. , including cost of materials, labour, curing, polishing complete as per specifications.	Sqm	57.83	1199.00	Rupees One Thousand One Hundred Ninety Nine Only

For K. DAMODAR & CO.